

AD659102

JM:bt
BBG-7
Flight Tests
STV-2

Classification change **Confidential**
UNCLASSIFIED
Per auth: *Office Sec Defense*
etc
NO OBJECTION TO PUBLICATION OF
OF MILITARY SECURITY
APL File No. **9** 11 APR 1958

APL-JHU/CM-409
September 10, 1947
Copy No. *6*

APL
CM-409

TO: G. C. Munro
FROM: J. Metzler

OFFICE OF SECURITY REVIEW (OASD L&PA)
DEPARTMENT OF DEFENSE

DDC
RECEIVED
OCT 11 1967

SUBJECT: Flight Tests of First Ten STV-2's With Program Roll Systems

REFERENCES: (a) NOTS Letters to APL-JHU Reporting STV-2 Tests:-
NP45/A9/F41-18/156/RO/AEF/meh, Serially Numbered:
#6, Fired 5 Sept 1946 - Serial (048) Jan 23, 1947
#7, Fired 25 Sept 1946 - Serial (0100) Feb 25, 1947
#24, Fired 29 Oct 1946 - Serial (0108) Feb 28, 1947
#17, Fired 16 Jan 1947 - Serial (0208) Apr 17, 1947
#14, Fired 23 Jan 1947 - Serial (0248) May 12, 1947
#1 #3, Fired 13-19 Jan 1947 - Serial (0229) Apr 30, 1947
#11 #10, Fired 20 Feb 1947 - Serial (0230) Apr 30, 1947
#25, Fired 26 Feb 1947 - Serial (0207) Apr 17, 1947

(b) STV-2 Data - APL-JHU Drawing No. 2400.

ENCLOSURE: (A) Figures 1-11. Figures 1-10 are telemetering curves, chiefly rate of roll versus deflection, some with missile speed or roll attitude included. Figure 11 is a typical set of telemetering curves of pressures and speeds from two receiving stations and camera data for comparison.

SUMMARY:

(1) Direction of Roll Response

<u>Supersonic</u>	<u>Subsonic</u>	<u>Differentially Deflecting Surfaces</u>
Reverse Roll	Reverse Roll	Rollerons
Reverse Roll	As Predicted	Wing Deflection
As Predicted	As Predicted	Tail Deflection

(2) Amount of Roll Response

At a speed of 1400 feet per second, the roll response was about 130°/sec., per degree of deflection per square foot of deflecting surface. At speed of 1400 ft/sec.:
Total effectiveness of rollerons is about 400 sec⁻²
Total effectiveness of deflected wings is about 1400 sec⁻²

(3) Roll Damping

a \approx about 12 sec⁻¹. Steady state was reached about 0.5 second after deflection of flap. Misalignments and gradual drift made measurements difficult.

20

Reproduced by the
CLEARINGHOUSE
for Federal Scientific & Technical
Information Springfield Va. 22151

THIS DOCUMENT HAS BEEN APPROVED
FOR PUBLIC RELEASE AND SALE: ITS
DISTRIBUTION IS UNLIMITED.

~~Confidential~~

JM:bt

-2-

APL-JHU/CM-409

(4) Accuracy of Records

Although differences were observed on all duplicate telemetering channels, comparisons with measurements by other methods were possible in the case of measurement of speed by ram pressure, Figure 11, Enclosure (A). Discrepancies of about 15 per cent were found between stations and between methods.

Purpose of This Report

Preliminary data, Reference (a), have been issued by NOTS, Inyokern, and CVAC on ten STV-2's with roll systems. It is the purpose of this report to analyze the data from these test to determine aerodynamic parameters. This report is based on the final data from telemetering and theodolite information.

General Purpose of These Flight Tests

Apart from the purposes of checking the operational characteristics of a revised inter-rocket manifold, of studying separation, and of determining operational effects of the launcher's elevation 10° higher (to 30°) with a 10 foot extension (to 35 feet) all of which were reported satisfactory, the main purposes of these flight tests of roll systems were as follows:

To provide a sustained velocity region of flight; and in this region to determine the rate of roll, the rate of change of rolling velocity resulting from differentially deflecting surfaces (1) at fixed angles and (2) with programmed movement, and to determine the damping in roll and the effectiveness of the roll control surface.

General Description and Configuration of STV-2

For details of the general configuration of STV-2, see the drawing of Reference (b).

The STV-2 is a projectile-shaped test vehicle 120 inches long with a diameter of 12 inches. Seventy-five (75) inches back from the point of the long tapered nose there are four movable wings having a span of 36 inches and a total area of 1.78 square feet. These wings are untapered, unswept, basically rectangular in planform, with tips having positive rake. At the rear there are four swept-back fixed fins having a span of 41 inches and a total area of 6 square feet.

Deflecting surfaces consist of two rollerons having a span of 26 inches and a total area of 0.28 square feet, or of the two horizontal wings or tail fins, which (except the tail fins) are differentially actuated by the electro-hydraulic system, changing deflection every 1-1/2 seconds. These movements are regulated by a bang-bang control system consisting of a clock mechanism which is electrically started at separation from the booster carriage.

Inside the afterbody of the vehicle, a slow burner ABL rocket having a diameter of ten inches, a rated thrust of 1000 pounds, and a rated duration of 10 seconds, is electrically fired at separation.

This document contains information affecting the national defense of the United States within the meaning of the Espionage Act, U.S.C., 31 and 32, and the transmission or the revelation of its contents in any manner to an unauthorized person is prohibited by law.

~~Confidential~~

JM:bt

-3-

APL-JHU/CM-409

To record information, the vehicle operates four channels of APL FM Telemetering employing the following end instruments:

(A) Ram stagnation pressure gauge, (B) Position of the deflecting surfaces, (C) Rate of roll, and (D) Roll attitude.

General Results and Sources of Data

The chief sources of information are the telemetering records in the form of rolls of photographic traces, each roll with a custom prepared calibration card for the trace of each frequency channel. The flight and preflight records used by APL were made at the "Vagabond Lady" Station located beside the Stran-Steel hut near the launcher. (CVAC uses the records of the "Weary Willie" Station located in a telemetering truck at Tower 4, G-1 range, about 8000 feet down range, about 20° left of the firing line). Both stations were fully equipped with recording facilities. The data of these rolls were transferred to the graph sheets, Enclosure (A), by plotting points at every one-tenth second of flight during normal performance and at every one-twentieth second for the first 3 seconds and during rapid changes.

"Newsreel" Kodachrome 16 millimeter motion pictures are available. These show the STV-2 vehicle and booster carriage assembly, the launching, the flight, and the recovery of the expended unit. Checks on the roll characteristics of the vehicle while attached to and separating from the booster carriage were obtained by examination of these newsreels.

Memoranda and data by CVAC and NOTS, included in Reference (a), have been freely used and copied. These include descriptions of test vehicles and test conditions, theodolite camera curves, and the Test Firing Reports which apparently are copies of original field data sheets.

Aerodynamic Coefficients. The simplified equation for the response in roll of a missile is:

$$I \ddot{\phi} + A \dot{\phi} = L$$

where ϕ = Angle of Roll

I = Moment of Inertia of Missile About Roll Axis

A = Aerodynamic Torque Due to Roll Angular Velocity

L = Torque (Producing Roll)

where A and L are constant for constant speed and altitude.

Dividing by I gives: $\ddot{\phi} + a \dot{\phi} = K$

where

$$a = \frac{A}{I}$$

$$K = \frac{L}{I}$$

This document contains information the disclosure of which in any manner to an unauthorized person is prohibited by law.

~~Confidential~~

JM:bt

-4-

APL-JHU/CM-409

For constant missile velocity and altitude and a fixed control surface setting, L is a constant, hence, under these conditions

$$\dot{\phi} = \frac{K}{a} + ce^{-at}$$

c being a constant depending on the initial conditions, and

$$\ddot{\phi} = -ace^{-at}$$

It is unlikely that all of the ideal conditions ever would be obtained. This approximate equation may, however, be used to obtain values of a and K . The following graphic method has been used. Starting at a time when a bang-bang deflection of the roll control surfaces has just been completed and ending when the new steady state of roll is reached, the telemetering record of rate gyro, $\dot{\phi}$, is plotted versus time as a large scale curve. The function $\dot{\phi}$ is graphically measured along this curve, and the corresponding $\ln|\dot{\phi}|$ is plotted producing a roughly straight line, the slope of which is $-a$. The possible effect of deceleration and change in pressure was examined and found negligible because of the short space of time in which calculations were made.

The STV-2's did not contain angular accelerometers, but a fair estimate of the angular acceleration can be obtained from the rate of roll. Examination of a number of the telemetering records has shown that, for the STV-2,

$$a \approx 12 \text{ sec}^{-1}$$

when the speed is 1400-1500 feet per second. Individual measurements ranged from about 6 to 15 seconds⁻¹.

The value of K depends on the magnitude of the roll control surface deflection, as well as on the surface being used for roll control and can be found from the relation

$$K = a \dot{\phi}_s$$

where

$\dot{\phi}_s$ = Steady state roll angular velocity, provided information on a and $\dot{\phi}_s$ is available.

In the case of the STV-2, the steady state is reached within about 0.5 second after the roll control surface assumed a new deflection.

Values of K are tabulated in the following page

Roll Response. Response to differentially deflected rollerons and wings was measured by the difference in the steady rate of roll before and after their deflection. This was done at 1400 feet per second (for deflections at the wing location) because this was the only speed at which data on five vehicles were available without extrapolation. Measurement of the sixth vehicle was prevented by failure to obtain good data. Measurements are tabulated below:

Speed at Which Response Was Measured Ft/Sec	STV-2 Serial Number	Degr. Defl.	Total Response Deg/Sec	Response According To CVAC Report CF-650		Response (Col 4) Per Deg.Defl. Surfaces Deg/Sec	Effectiveness of Roll Control Surfaces a 1/4 - K	Response (Col 7) /sq ft Surface Deflected Deg/Sec
				Flight	Theory			
				Deg/Sec	Deg/Sec			

Inter-Wing Rollers - Standard STV-2's -- Area: 0.28 Square Feet

1400	No. 24	10.0°	-242	-335	300	-24	-290	-86
1400	No. 17	3.6°	-126	-135	175	-35	-420	-124
1400	No. 14	2.2°	-80	-60	100	-36	-430	-130

Deflected Wings - Area: 0.89 Square Feet

1400	No. 10	5.0°	-580	-460	930	-116	-1300	-131
1400	No. 11	3.3°	-410	-335	620	-124	-1500	-139
1400	No. 13	1.3°	No Data	No Data	240	---	---	---

NOTE: With regard to the values in the last column, it may be accidental that the standard rollers and the deflected wings do not show more difference in response per unit area. If they may be considered together, (except at 10° rolleron deflection where the response falls off by one-third) they produce an average roll response of approximately 1300 per second, per degree of deflection per square foot of deflecting surface.

Forward Rollers - Area: 0.28 Square Foot

1100	No. 1	10.0°	-11	These were CAL		-1	-12	-4
1200	No. 25	12.5°	-160	Constructed Units		-13	-160	-47

NOTE: It may be noted that the response from forward rollers is small and may be variable.

Confidential

CM-409

Confidential

JM:bt

-6-

APL-JHU/CM-409

Angles of Attack and Yaw. If yaw and pitch were present, they were not of sufficient magnitude to be detected by the methods of observation used. No further discussion of pitch and yaw angles is included.

Booster Inter-Rocket Manifold. It has been reported that the introduction of solid steel inter-rocket manifold into the booster was satisfactory.

Launching at Invokern. It has been reported that launching at an elevation of 30° with a 35 foot guide rail was satisfactory.

Forward Rolleron System, Mk. 50, Mod. 1, (CAL Construction)

Description and Programs of Deflections. Vehicles STV-2 No. 1 and No. 25 were assembled by the Cornell Aeronautical Laboratory. Located 21.15 inches back from the nose were two rollerons, Reference (a), with tips having positive rake. These were actuated cyclically by the electro-hydraulic control system about one second after separation and at successive intervals of one second. The amplitudes of successive deflections were altered by a cam which allowed the bell crank to go a distance depending on the position of the cam. The movement of the hydraulic piston was stopped against this bell crank. The cam was moved into successive positions by a ratchet device and a motor driven clock mechanism. These movements turned out to be somewhat mixed but were programmed roughly along the following lines:

<u>Vehicle</u>	<u>Program of Deflections</u>
Serial No. 1	$3\frac{1}{3}^\circ$ cw, $3\frac{1}{3}^\circ$ ccw, $6\frac{2}{3}^\circ$ ccw, $6\frac{2}{3}^\circ$ cw, 10° ccw, 10° cw;
Serial No. 25	5° cw, 15° ccw, 15° cw, 5° ccw, 15° cw, 10° ccw

Results: Forward Rollerons Ineffective. Compared to other configurations for producing rolling torques, the forward rollerons were ineffective in degree of response produced.

Both vehicles showed "reverse roll"* at all speeds.

The aerodynamic roll damping coefficient, a_r , was computed for No. 1 only, at one of the program changes which produced counterclockwise roll response, when the speed was 1500 feet per second. The value obtained was $a_r \approx 7$ (rough approximation)

* By "reverse roll" is meant a response tending to roll the vehicle in the reverse direction to that predicted in consideration of the deflected surfaces alone.

Confidential

JM:bt

-7-

APL-JHU/CM-409

Inter-Wing Rolleron System (CVAC Construction of Standard STV-2)

Description and Program of Deflections. Vehicles STV-2 No. 24, No. 17, and No. 14 were assembled by the Consolidated-Vultee Aircraft Corporation as indicated precisely in the drawing of Reference (b). Their rollerons were located at the forward wing position mounted 45° counterclockwise from the vertical wings when viewed from the rear. The rollerons were differentially rotated by a bang-bang roll control system which reversed their deflection at separation (in the case of No. 14, this was delayed for 1 1/2 seconds) and at successive 1 1/2 seconds intervals thereafter (in the case of No. 24, this was at 2 1/2 seconds intervals). The amplitude of movement of the hydraulic piston was controlled by a restraining stop in the cylinder. The movements followed the following programs.

<u>Vehicle</u>	<u>Program of Deflections</u>
Serial No. 24	10° cw, 10° ccw, and so on.
Serial No. 17	3° 38' cw, 3° 38' ccw, and so on.
Serial No. 14	2° 12' cw, 2° 12' ccw, and so on.

Results: Inter-Wing Rollerons Somewhat Effective. Inter-wing rollerons effected reverse roll at all speeds. See table in the General Results, Paragraph 4-b.

The aerodynamic coefficient, a , was computed by selecting a vehicle, STV-2 No. 24, which had what was considered to be fairly uniform rate gyro curves (of response to rolleron deflection). After 8.3 seconds of flight, when the rolleron deflection rotated the vehicle in a counterclockwise direction, at a missile speed of about 1400 feet per second, a damping coefficient of $a \pm 12$ was computed.

Further calculations were made on STV-2 No. 17. After 10.4 seconds of flight, when the rolleron deflection rotated the vehicle in a counterclockwise direction, and when the speed was about 1350 feet per second, a damping coefficient of $a \pm 11$ was obtained.

After 7.9 seconds of flight, when the rolleron deflection rotated the vehicle in a clockwise direction, and when the speed was about 1400 feet per second, the value of a was $a \pm 6$.

Horizontal Wing Roll System (CVAC Construction)

Description and Program of Deflection. Vehicles STV-2 No. 13, No. 11, and No. 10 were assembled by the Consolidated-Vultee Aircraft Corporation with no rollerons or ailerons. The horizontal wings were differentially rotated by a bang-bang roll control system which reversed their deflection about 1 1/2 seconds after separation, and at 1 1/2 second intervals thereafter. The amplitude of the movement of the hydraulic piston was made constant by a stop in the cylinder. The movements followed the following programs.

[Handwritten signature and stamp]

~~Confidential~~

JM:bt

-8-

APL-JHU/CM-409

<u>Vehicle</u>	<u>Program of Deflections</u>
Serial No. 13	1° 20' ccw, 1° 20' cw, and so on
Serial No. 11	3° 20' ccw, 3° 20' cw, and so on
Serial No. 10	5° ccw, 5° cw, and so on

Results of Horizontal Wing Roll System. All three vehicles showed reverse roll at supersonic speeds. At subsonic speeds, No. 11 and No. 10 had direction or roll as predicted for the wing deflections alone. (A record on No. 13 at subsonic speed was not obtained).

See table in General Results, Paragraph 4-6. The aerodynamic coefficient was not computed.

Horizontal Tail With Differential Deflection (CVAC Construction)

Description. In No. 7 there were no rollerons or ailerons. The horizontal tail fins were set with a differential deflection of 1° in a clockwise direction (this being the direction of their rotation as seen from outside the test vehicle looking along the axis of rotation of the particular surface).

Results of Horizontal Tail Roll System. At both supersonic and subsonic speeds, No. 7 rolled fairly steadily at about 2 1/2 r.p.s. in a clockwise direction as viewed from the rear of the vehicle. This is the direction of roll as predicted for the tail deflecting surfaces alone. In this connection it may be noted that this is the only vehicle which did not have reverse roll. The tail deflection was calculated to approximate the maximum misalignment to be expected from manufacturing tolerances. The resultant roll was greater than the greatest roll response to 5° differential deflection of the horizontal wings. It is not known how much of this was due to the deflecting surfaces and how much was caused by further accidental misalignment.

Speed Measurement by Stagnation Pressures

It appears that telemetered stagnation pressure can be a good method of measuring vehicular speed, provided the free stream pressure is known.

Stagnation pressure gauge readings were telemetered from seven of the ten STV-2's. Curves of supersonic speed versus time of flight were prepared from these data, after calculating the speed by the use of Rayleigh's pilot-tube formula. Ambient pressures taken directly from meteorological data obtained at the field at the time of flight, when available in Reference (a), were found to follow the normal curve of pressure versus altitude within 2 or 3 millibars. Under such conditions, in the measurement of speed by stagnation pressure, the free stream pressure may be taken from the normal curve, using the altitude obtained from the theodolite data and correcting for the atmospheric pressure at the surface. In comparing speeds with those obtained from camera data, head and tail winds were taken into consideration, although the weather was fairly calm, these made corrections up to 20 feet per second.

~~CONFIDENTIAL~~
This document contains information of a classified nature and its transmission or disclosure in any form is prohibited by law.

~~Confidential~~

JM:bt

-9-

APL-JHU/CM-409

Accuracy of Telemetric Data

The accuracy of telemetric data can not be checked completely by comparison with other methods of observation, although it has been noted that there are variations between duplicate channels on apparently fixed values such as flap settings, also variations between the records of the two receiving stations.

Ram pressure gauge readings provide a means by which speeds computed from their telemetric data can readily be compared with the speeds measured by triangulation of theodolite camera data and by acceleration camera data.

Each curve of speed calculated from ram pressure (Paragraph 9) was plotted along with the corresponding theodolite camera and acceleration camera velocity curves for comparison. In making the comparison, acceleration camera data when available was used in preference to theodolite data. In most of these curves, the curve of speed calculated from pressure runs roughly parallel to that from camera data but is different from the latter by 90 feet per second (on the average). This difference corresponds to a pressure difference of about 3 1/2 pounds per square inch. The two telemetering records of this same function for each flight, moreover, differ on the average about this same amount from each other. On comparison of the records of 4 vehicles, No. 7, No. 17, No. 13, and No. 10, the average difference between stations was about 3 pounds per square inch in 20, or about 15 per cent.

Figure 11 of Enclosure (A) is a typical set of curves of the two records of ram pressure gauge readings, (1) from the "Vagabond Lady" telemetering records and (2) from CVAC data read from the "Wearie Willie" records. The corresponding speeds are also plotted, with two speed curves from camera data for comparison. Differences between all four curves in Figure 11 may be noted.

Recommendations

In order to get the most information and the most reliable information from a necessarily budgeted minimum of flight tests, (1) it has been recommended that critical preflight data so far as practicable be precisely recorded by two or more independent proved-in source, employing two or more basic methods of observation, e.g. that records of flap deflections be made by both visual inspection and by photography simultaneously with the calibration of both telemetering receivers; and (2) it has been recommended to telemeter, at periodic short intervals during flight, steps of calibration of each end instrument.

J. Metzler

~~Confidential~~
This document contains information which is exempt from release under the provisions of the National Defense Information Act, 50 U.S.C. 3605 (a) (1) (A) and (2) (A). The unauthorized disclosure of its contents in any manner to an unauthorized person is prohibited by law.

-12-

1. This document contains information reflecting the national defense of the United States within the meaning of the Espionage Act, 50 U.S.C. 1835, and 22 U.S.C. 2141, and the unauthorized disclosure of contents in any manner to an unauthorized person is prohibited by law.

~~CONFIDENTIAL~~

FIG 1

STV-2A #6 CVAC MK 54 MOD 2

FIRE AT RANGE G-1 NOTS, INYOKERN 5 SEPT 1946

RD. 2 TR X1157 INTER-WING ROLLERONS DEFLECTED 10° CW

RATE GYRO

RATE OF ROLL vs. TIME

00 CW DEGREES/SECOND

TIME IN SECONDS

CM-409

This document contains information of a classified nature. It is to be controlled and its use restricted to personnel authorized to receive it. It is to be destroyed when it is no longer needed for official use. It is to be handled in accordance with the instructions of the Department of Defense. It is to be stored in a secure place and its use is to be limited to the purpose for which it was prepared. It is to be destroyed when it is no longer needed for official use. It is to be handled in accordance with the instructions of the Department of Defense. It is to be stored in a secure place and its use is to be limited to the purpose for which it was prepared.


KUPFER & KUPFER CO., N.Y. NO. 359-11
100-10 31st St. In b. killed service
Serving in U.S.A.
MADE IN U.S.A.

CONFIDENTIAL

FIG. 2

STV-2A #7 CVAC MK. 54 MOD. 3
FIRED AT RANGE G-1 NOTS, INYOKERN 25 SEPT. 1946
RD. 1 TR XII73 TAIL DEFLECTION 1° CW
RATE OF ROLL VS. TIME

RATE GYRO



CONFIDENTIAL

CM DEGREES CCW




FIG 3 STV-2A #24 CVAC MK.58 MOD 2
 FIRED AT RANGE G-1 NOTS, INYOKERN 29 OCT. 1946
 RD. 1 TR X1202 INTER-WING ROLLERONS
 RATE OF ROLL AND ROLL ACCELERATION VS. TIME
 WITH PROGRAMMED MOVEMENT OF INTER-WING ROLLERONS $\pm 10^\circ$


This diagram shows the roll rate and roll acceleration of the aircraft during the test. The roll rate is shown in degrees per second and the roll acceleration is shown in g's. The aircraft was rolled $\pm 10^\circ$ and the roll rate and acceleration were recorded. The aircraft was rolled $\pm 10^\circ$ and the roll rate and acceleration were recorded.

~~CONFIDENTIAL~~


FIG. 4

17 CVAC MK 58 MOD. 2
STV-2A
FIRING AT RANGE G-1 NOTS, INYOKERN 16 JAN. 1947
RD. 1 TR X1242 INTER-WING ROLLERONS
PROGRAMMED MOVEMENT OF ROLLERONS $\pm 3^{\circ} 36'$

RATE OF ROLL VS TIME



~~CONFIDENTIAL~~



~~CONFIDENTIAL~~

FIG. 6

STV-2A #1 CAL MK 58 MOD. I
 FIRED AT RANGE G-1 NOTS, INYOKERN 13 FEB. 1947
 RD. 1 TR X1246 FORWARD ROLLERONS
 PROGRAMMED MOVEMENT OF ROLLERONS $\pm 31^\circ$ TO $\pm 10^\circ$


RATE OF ROLL AND ROLL ATTITUDE VS. TIME

ROLLERON

RATE GYRO

ROLL GYRO

0 100 200
 DEG/SEC
 CMW DEGREES
 CMW DEGREES



MACH NO. 1

DEGREES

180

CM-449

TIME IN SECONDS

DEB. CW



FIG. 7 STV-2A #13 CVAC MK 58 MOD. 3


FIRE AT RANGE G-I NOTS. INYOKERN 19 FEB 1947

RD 2 TR X1246


WING DEFLECTIONS

HORIZONTAL WINGS DEFLECTED 1° 20' CW


SPEED OF VEHICLE vs. TIME



CONFIDENTIAL



CONFIDENTIAL



17 x 10 to the 14 inch, 5th. Area: 100000
 1000000, 1 x 10 in.
 1000000, 1 x 10 in.
 1000000, 1 x 10 in.

CONFIDENTIAL


FIG. 11 STV-2A #17 QVAC MK. 58 MOD. 2

FIRE AT RANGE G-1 NOTS, INYOKERN 8 JAN. 1947

RD. 1 TR X1232 SPEED BY RAM STAGNATION PRESSURE

SPEED OF VEHICLE VS. TIME

RAM STAGNATION PRESSURE IN LBS./SQ. IN.



Metzler, J

DIVISION: Guided Missiles (1)

SECTION: Testing (14)

CROSS REFERENCES: Missiles, Guided - Flight tests
(62929); Roll (83000)

LTI- 12649

ORIG. AGENCY NUMBER

CM-409

REVISION

AUTHOR(S)

AMER. TITLE: Flight tests of first ten STV-2's with program roll systems

FORG'N. TITLE:

ORIGINATING AGENCY: Johns Hopkins Univ., Applied Physics Lab., Silver Spring, Md.

TRANSLATION:

COUNTRY	LANGUAGE	FORG'N. CLASS.	U. S. CLASS.	DATE	PAGES	ILLUS.	FEATURES
U.S.	Eng.			Sep'47	20	12	table, graphs

ABSTRACT

Report presents a description and configuration of the supersonic test vehicle and equipment used during the tests. The main purpose was to provide a sustained velocity region of flight, to determine the rate of roll and rate of change of rolling velocity resulting from differentially deflecting surfaces at fixed angles and to determine damping in roll and effectiveness of roll control surface. Results obtained from telemetering records in the form of rolls of photographic traces are evaluated.